



NOTES:

1. INSTALL TREE PROTECTION BARRIER BEFORE SITE CLEARING AND INITIATION OF CONSTRUCTION.
2. MAINTAIN TREE PROTECTION BARRIER DURING CLEARING AND SITE CONSTRUCTION.
3. KEEP AREA WITHIN OR AGAINST PROTECTION BARRIER CLEAR OF BUILDING MATERIALS, LITTER AND STANDING WATER.
4. DO NOT DISTURB EXISTING GRADES WITHIN TREE PROTECTION AREA FOR PROTECTED RETAINED TREES.
5. THE DEVELOPER IS RESPONSIBLE FOR MAINTENANCE WITHIN TREE PROTECTION BARRIER. DAMAGED TREES WILL BE REPLACED AT DEVELOPERS COST.
6. ANY DISRUPTION OR PLANTING WITHIN TREE PROTECTION AREA IS TO BE SUPERVISED BY THE PROJECT ARBOURIST OR LANDSCAPE ARCHITECT.
7. RETAINED TREES TO BE WATERED AT THE DIRECTION OF THE CONSULTING ARBOURIST/LANDSCAPE ARCHITECT.

				THE CORPORATION OF DELTA ENGINEERING DEPARTMENT			DSN.	DRN. M.M.	DWG. No.								
							CHKD.	APVRD.	L11-4								
<table border="1"> <thead> <tr> <th>DATE</th> <th>REVISION</th> <th>No.</th> <th>BY</th> </tr> </thead> <tbody> <tr> <td colspan="4">REVISIONS</td> </tr> </tbody> </table>				DATE	REVISION	No.	BY	REVISIONS				TREE PROTECTION DETAIL			SCALE	N.T.S.	
				DATE	REVISION	No.	BY										
REVISIONS																	
DATE	2015-04-09	RVSN.															